Notification dated 8th August 1939.

Notice is hereby given that sealed tenders will be received at the office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 28th August 1939, for "Improving Distribution System of Water Supply for giving facilities for granting house connections at Arsikere." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1939.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 160 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for Improving Distribution System of Water Supply for giving facilities for granting house connections at Arsikere," in default of which tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Abstract estimate of quantities of work for improving distribution system of water-supply for giving facilities for granting house connections at Arsikere.

No.	Particulars	Unit	Quantity
1	Laying and jointing 1½" G. I. pipes with cuts and threads including earthwork and fixing of specials	R.ft.	11,020
2	Do do 1"	,,	6,000
3	Making lead joints to 3" C. I. pipes	No.	40
4	Fixing C. I. valves and collars	,,	11

N. KRISHNIENGAR,
Sanitary Engineer.

KOLAR DIVISION.

Abstract Notification 31*st July* 1939.

The attention of the public is invited to the detailed notification, published on pages 1493-1495, Part VI of the *Mysore Gazette*, dated 3rd August 1939, *re* tenders for the maintenance work to Muduvathi Doddakere Register No. 199/780 of Kolar Taluk (Major Tank).

The last date for receiving tenders is 30th August 1939.

Notification dated 8th August 1939.

1. Sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M. on 4th September 1939, for constructing a building for Dispensary at Kylanoor, Kolar Taluk.

2. Tenders in the prescribed form obtainable from the office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover

and superscribed as "Tender for constructing Dispensary Building." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury challan for earnest money of Rs. 270 paid to the Treasury to the credit of 17(c) P. W. Deposits against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 4th September 1939 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931). A reserve of 5% will be held in the works bills of the contractor and the same will be repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs.....

9. Specific rates should be given for each item in the schedule accompanying the [illegible] and the rates should be in rupees, annas and pies and expressed both in words [illegible] Tenders offering a percentage reduction on the [illegible] amount will be rejected.

10. Any rates or lumpsum amounts for [illegible] called for, if tendered by the tenderer, will not be taken notice of. The rates for such [illegible] may be [illegible] agreement schedule with date and reasons for the same. Where lumpsum provisions [illegible] of quantities the contractor will be paid at either his tendered rates for each item [illegible] ruling schedule of rates in the Division.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of May 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the

date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary, provide for the same by insurance at the proper time.

Note—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.
(*c*) Copies of tenders in the prescribed form are obtainable from the office of the Executive Engineer, Kolar Division, Kolar, only on payment of 0-4-0 per form.

Abstract of modified quantities for constructing a building for Dispensary at Kyalanoor, Kolar Taluk.

Sl. No.	Description of work	Per	Rate	Quantity	Rate to be offered
	Main Building.		Rs. a. p.		Rs. a. p.
1	Earthwork excavation for foundation filling in basement	C.yd.	0 2 6	78	
2	Laying stone jelly concrete in lime mortar ..	C.ft.	0 3 6	505	
3	Size stone in mud (bonds)	,,	0 3 3	3830	
4	Burnt brick in mud superstructure	,,	0 3 0	218	
5	Cut stone pillars 10″ sqr. and 10′ to 10½′ high, 3 line dressed complete as per design ..	No.	20 0 0	4	
6	Burnt stone slabs 6″ thick dressed and fixed including extra dressing to exposed surfaces ..	S.ft.	0 4 0	515	
7	Providing teakwood doors with panelled shutters with bolts, hinges and pad locks, etc., complete	,,	1 4 0	140	
8	Providing teakwood windows with panelled shutters and divided into 4 halves including iron bars, hooks and eyes, etc., complete ..	,,	1 8 0	108	
9	Providing T. W. glazed ventilators including iron bars, etc., complete	,,	1 2 0	12	
10	Plastering with chunam mortar inside & round ..	Sqr.	3 0 0	21.06	
11	White washing two coats as per plastering inside ..	,,	0 4 0	21.06	
12	Pointing with cement mortar	Sqr.	3 0 0	14·78	
13	Flooring with concrete 3″ thick including cement plastering and red colouring, etc., complete ..	,,	15 0 0	6.50	
14	Constructing ornamental parapet with balustrades as per design	R.ft.	0 8 0	118	
15	Providing sun shades over doors	No.	3 0 0	9	
16	Roofing with R. B. C. including tension and compression bars and plastering at top and bottom and finished neatly as per standard specification	Sqr.	60 0 0	8.85	
17	R. S. beams including hoisting and fixing with a punic coat of anti-corrosive paint (12″×5″) at 30 lbs.	Cwt.	14 8 0	10½	